

This Page Is Inserted by IFW Operations
and is not a part of the Official Record

BEST AVAILABLE IMAGES

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images may include (but are not limited to):

- BLACK BORDERS
- TEXT CUT OFF AT TOP, BOTTOM OR SIDES
- FADED TEXT
- ILLEGIBLE TEXT
- SKEWED/SLANTED IMAGES
- COLORED PHOTOS
- BLACK OR VERY BLACK AND WHITE DARK PHOTOS
- GRAY SCALE DOCUMENTS

IMAGES ARE BEST AVAILABLE COPY.

As rescanning documents *will not* correct images,
please do not report the images to the
Image Problem Mailbox.

PATENT COOPERATION TREATY

PCT

NOTIFICATION OF ELECTION

(PCT Rule 61.2)

From the INTERNATIONAL BUREAU

To:

Assistant Commissioner for Patents
United States Patent and Trademark
Office
Box PCT
Washington, D.C. 20231
ETATS-UNIS D'AMERIQUE

in its capacity as elected Office

Date of mailing (day/month/year)

03 July 2000 (03.07.00)

International application No.

PCT/US99/25427

Applicant's or agent's file reference

021239-040

International filing date (day/month/year)

29 October 1999 (29.10.99)

Priority date (day/month/year)

29 October 1998 (29.10.98)

Applicant

KOLLER, Kent, B. et al

1. The designated Office is hereby notified of its election made:



In the demand filed with the International Preliminary Examining Authority on:

25 May 2000 (25.05.00)



In a notice effecting later election filed with the International Bureau on:

2. The election ☒ was☐ was not

made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

The International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland

Facsimile No.: (41-22) 740.14.35

Authorized officer

Manu Berrod

Telephone No.: (41-22) 338.83.38

Docket No.: 021239-040

International Application Number : PCT/US99/25427

International Filing Date : 29 October 1999

Priority Date : 29 October 1998

Title: FILTER FOR SELECTIVE REMOVAL OF A GASEOUS COMPONENT

REQUEST TO CHANGE NAME AND ADDRESS OF APPLICANT
UNDER PCT RULE 92bis

VIA FACSIMILE

PCT/WIPO
34 chemin de Colombettes
CH-1211 Geneva 20
SWITZERLAND

Sir:

This application initially was filed in the United States Receiving Office in the name of the applicant identified below:


PHILIP MORRIS INCORPORATED
120 Park Avenue
New York, New York 10017, US.

Please change the name and address of the applicant to read as follows:

PHILIP MORRIS PRODUCTS INC.
3601 Commerce Road
Richmond, Virginia 23234, US.

We ask that you record these changes upon the Request, and that you notify the International Searching Authority and the designated Offices. Please be certain that these changes are recorded prior to the Article 39(1) time limit for national phase filings. Also, please confirm safe receipt of these documents, in due course. Attached is a Power of Attorney, executed on behalf of Philip Morris Products Inc.

Respectfully submitted,

A handwritten signature in black ink, appearing to read "Peter K. Skiff". The signature is fluid and cursive, with the first name "Peter" and last name "Skiff" clearly distinguishable.

Peter K. Skiff
Attorney for Applicant

Date: 25 May 2000

BURNS, DOANE, SWECKER & MATHIS, L.L.P.

P.O. Box 1404
Alexandria, Virginia 22313-1404
United States of America

Telephone: (703) 836-6620

cc: RO/US

IN THE UNITED STATES RECEIVING OFFICE (RO/US)

Box PCT

Commissioner of Patents and Trademark

Washington, D.C. 20231

**APPOINTMENT OF REPRESENTATIVE FOR
INTERNATIONAL APPLICATION**

The undersigned applicant hereby appoints:

SKIFF, Peter K.; BROWN, Harold R. III; HUNTLEY, David M.
and DU BOIS, Steven M. of
Burns, Doane, Swecker & Mathis, L.L.P.
P.O. Box 1404
Alexandria, Virginia 22313-1404 (US)
Telephone (703) 836-6620

to act on its behalf before the competent international Authorities in connection with any and
all International Applications filed by the corporation and of which it is the applicant and to
receive payments on its behalf.

Richmond, VA

Place

August 14, 1998

Date

PHILIP MORRIS PRODUCTS INC.


by: A. Stephen Roberts
Title: A. Stephen Roberts
Vice President

PATENT COOPERATION TREATY

From the
INTERNATIONAL PRELIMINARY EXAMINING AUTHORITY

To: PETER K. SKIFF
BURNS, DOANE, SWECKER & MATHIS, L.L.P.
P.O. BOX 1404
ALEXANDRIA, VA 22313-1404

DOCKETED



NOTIFICATION OF TRANSMITTAL OF INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Rule 71.1)

Date of Mailing (day/month/year)		11 JAN 2001
Applicant's or agent's file reference 021239-040		IMPORTANT NOTIFICATION
International application No. PCT/US99/25427	International filing date (day/month/year) 29 OCTOBER 1999	Priority Date (day/month/year) 29 OCTOBER 1998
Applicant PHILIP MORRIS INCORPORATED		

1. The applicant is hereby notified that this International Preliminary Examining Authority transmits herewith the international preliminary examination report and its annexes, if any, established on the international application.
2. A copy of the report and its annexes, if any is being transmitted to the International Bureau for communication to all the elected Offices.
3. Where required by any of the elected Offices, the International Bureau will prepare an English translation of the report (but not of any annexes) and will transmit such translation to those Offices.
4. **REMINDER**

The applicant must enter the national phase before each elected Office by performing certain acts (filing translations and paying national fees) within 30 months from the priority date (or later in some Offices)(Article 39(1))(see also the reminder sent by the International Bureau with Form PCT/IB/301).

Where a translation of the international application must be furnished to an elected Office, that translation must contain a translation of any annexes to the international preliminary examination report. It is the applicant's responsibility to prepare and furnish such translation directly to each elected Office concerned.

For further details on the applicable time limits and requirements of the elected Offices, see Volume II of the PCT Applicant's Guide.

Name and mailing address of the IPEA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231 Facsimile No. (703) 305-3230	Authorized officer DIONNE A. WALLS Telephone No. (703) 308-0661
--	---

The demand must be filed directly with the competent International Preliminary Examining Authority if two or more Authorities are competent, with the one chosen by the applicant. The name or two-letter code of that Authority may be indicated by the applicant on the line below:

IPEA/ US

CHAPTER II

**PCT
DEMAND**

under Article 31 of the Patent Cooperation Treaty:

The undersigned requests that the international application specified below be the subject of international preliminary examination according to the Patent Cooperation Treaty and hereby elects all eligible States (except where otherwise indicated).

For International Preliminary Examining Authority use only

Identification of IPEA	Date of receipt of DEMAND
------------------------	---------------------------

Box No. I IDENTIFICATION OF THE INTERNATIONAL APPLICATION		Applicant's or agent's file reference 021239-040
International application No. PCT/US99/25427	International filing date (day/month/year) 29 October 1999 (29.10.99)	(Earliest) Priority date (day/month/year) 29 October 1998 (29.10.98)
Title of invention Filter for Selective Removal of a Gaseous Component		

Box No. II APPLICANT(S)	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.) PHILIP MORRIS PRODUCTS INC. 3601 Commerce Road Richmond, Virginia 23234 US	Telephone No.: (804) 274-2045
	Facsimile No.: (804) 274-4780
	Teleprinter No.:
State (that is, country) of nationality: US	State (that is, country) of residence: US

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.) KOLLER, Kent B. 8401 Kintail Drive Chesterfield, Virginia 23838 US	
State (that is, country) of nationality: US	State (that is, country) of residence: US

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.) WRENN, Susan E. 12130 Ivy Mill Road Chesterfield, Virginia 23832 US	
State (that is, country) of nationality: US	State (that is, country) of residence: US

☒ Further applicants are indicated on a continuation sheet.

DOCKETED
filed 5/25/00
TB
L.F.

Continuation of Box No. II APPLICANT(S)

If none of the following sub-boxes is used, this sheet should not be included in the demand.

Name and address: (Family name followed by given name for a legal entity, full official designation. The address must include postal code and name of country.)

HOUCK, Willie G., Jr.
7753 Lake Forrest Drive
Richmond, Virginia 23235
US

State (that is, country) of nationality:
USState (that is, country) of residence
US

Name and address: (Family name followed by given name for a legal entity, full official designation. The address must include postal code and name of country.)

PAINE, John B. III
13630 Trilithon Road
Midlothian, Virginia 23235
US

State (that is, country) of nationality:
USState (that is, country) of residence
US

Name and address: (Family name followed by given name for a legal entity, full official designation. The address must include postal code and name of country.)

State (that is, country) of nationality:

State (that is, country) of residence

Name and address: (Family name followed by given name for a legal entity, full official designation. The address must include postal code and name of country.)

State (that is, country) of nationality:

State (that is, country) of residence

☐ Further applicants are indicated on another continuation sheet.

Box No. III AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCEThe following person is ☒ agent ☐ common representativeand ☒ has been appointed earlier and represents the applicant(s) also for international preliminary examination.☐ is hereby appointed any earlier appointment of (an) agent(s)/common representative is hereby revoked.☐ is hereby appointed, specifically for the procedure before the International Preliminary Examining Authority, in addition to the agent(s)/common representative appointed earlier.Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*SKIFF, Peter K.
Burns, Doane, Swecker & Mathis, L.L.P.
P.O. Box 1404
Alexandria, Virginia 22313-1404
United States of AmericaTelephone No.:
(703) 836-6620Facsimile No.:
(703) 836-2021

Teleprinter No.:

☐ Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.**Box No. IV BASIS FOR INTERNATIONAL PRELIMINARY EXAMINATION****Statement concerning amendments:***

1. The applicant wishes the international preliminary examination to start on the basis of:

☒ the international application as originally filedthe description ☐ as originally filed☐ as amended under Article 34the claims ☐ as originally filed☐ as amended under Article 19 (together with any accompanying statement)☐ as amended under Article 34the drawings ☐ as originally filed☐ as amended under article 342. ☐ The applicant wishes any amendment to the claims under Article 19 to be considered as reversed.3. ☐ The applicant wishes the start of the international preliminary examination to be postponed until the expiration of 20 months from the priority date unless the International Preliminary Examining Authority receives a copy of any amendments made under Article 19 or a notice from the applicant that he does not wish to make such amendments (Rule 69.1(d)). *(This check-box may be marked only where the time limit under Article 19 has not yet expired.)*

* Where no check-box is marked, international preliminary examination will start on the basis of the international application as originally filed or, where a copy of amendment to the claims under Article 19 and/or amendments of the international application under Article 34 are received by the International Preliminary Examining Authority before it has begun to draw up a written opinion or the international preliminary examination report, as so amended.

Language for the purposes of international preliminary examination: ENGLISH☒ which is the language in which the international application was filed.☐ which is the language of a translation furnished for the purposes of international search.☐ which is the language of publication of the international application.☐ which is the language of the translation (to be) furnished for the purposes of international preliminary examination.**Box No. V ELECTION OF STATES**The applicant hereby elects all eligible States *(that is, all States which have been designated and which are bound by Chapter II of the PCT)*

excluding the following States which the applicant wishes not to elect:

Box No. VI CHECK LIST

The demand is accompanied by the following elements, in the language referred to in Box No. IV, for the purposes of international preliminary examination:

For International Preliminary
Examining Authority use only

1.	translation of international application	:	sheets	<input type="checkbox"/>	<input type="checkbox"/>
2.	amendments under Article 34	:	sheets	<input type="checkbox"/>	<input type="checkbox"/>
3.	copy (or, where required, translation) of amendments under Article 19	:	sheets	<input type="checkbox"/>	<input type="checkbox"/>
4.	copy (or, where required, translation) of statement under Article 19	:	sheets	<input type="checkbox"/>	<input type="checkbox"/>
5.	letter	:	sheets	<input type="checkbox"/>	<input type="checkbox"/>
6.	other (specify)	:	sheets	<input type="checkbox"/>	<input type="checkbox"/>

The demand is also accompanied by the item(s) marked below:

- | | |
|--|---|
| 1. <input checked="" type="checkbox"/> fee calculation sheet | 4. <input type="checkbox"/> statement explaining lack of signature |
| 2. <input type="checkbox"/> separate signed power of attorney | 5. <input type="checkbox"/> nucleotide and or amino acid sequence listing in
computer readable form |
| 3. <input type="checkbox"/> copy of general power of attorney; reference number, if any: | 6. <input checked="" type="checkbox"/> other (specify): Request to Change Name and
Address of First Applicant under Rule 92bis |

Box No. VII SIGNATURE OF APPLICANT, AGENT OR COMMON REPRESENTATIVE

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the demand).


Signature Peter K. Skiff Registration No. 31,917

For International Preliminary Examining Authority use only


1. ☐ Date of actual receipt of demand
2. ☐ Adjusted date of receipt of demand due to CORRECTIONS under Rule 60.1(b):
3. ☐ The date of receipt of the demand is AFTER the expiration of 19 months from the priority date and item 4 or 5, below, does not apply. ☐ The applicant has been informed accordingly.
4. ☐ The date of receipt of the demand is WITHIN the period of 19 months from the priority date as extended by virtue of Rule 80.5.
5. ☐ Although the date of receipt of the demand is after the expiration of 19 months from the priority date, the delay in arrival is EXCUSED pursuant to Rule 82.

For International Bureau use only

Demand received from IPEA on:

FEE CALCULATION SHEET

Annex to the Demand for international preliminary examination

International application No. PCT/US99/25427	For International Preliminary Examining Authority use only	
Applicant's or agent's file reference 021239-040	Date stamp of the IPEA	
Applicant Philip Morris Products Inc.		
Calculation of prescribed fees		
1. Preliminary examination fee	490.00	<input type="checkbox"/> P
2. Handling fee (<i>Applicants from certain States are entitled to a reduction of 75% of the handling fee. Where the applicant is (or all applicants are) so entitled, the amount to be entered at H is 25% of the handling fee.</i>)	153.00	<input type="checkbox"/> H
3. Total of prescribed fees Add the amounts entered at P and H and enter total in the TOTAL box	\$643.00	<input type="checkbox"/> TOTAL
Mode of Payment		
<div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <input checked="" type="checkbox"/> authorization to charge deposit account with the IPEA (see below) </div> <div style="width: 45%;"> <input type="checkbox"/> cash </div> </div> <div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <input checked="" type="checkbox"/> cheque </div> <div style="width: 45%;"> <input type="checkbox"/> revenue stamps </div> </div> <div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <input type="checkbox"/> postal money order </div> <div style="width: 45%;"> <input type="checkbox"/> coupons </div> </div> <div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <input type="checkbox"/> bank draft </div> <div style="width: 45%;"> <input type="checkbox"/> other (specify): </div> </div>		
Deposit Account Authorization (<i>this mode of payment may not be available at all IPEAs</i>)		
The IPEA/ <u>US</u> <input type="checkbox"/> is hereby authorized to charge the total fees indicated above to my deposit account		
<input checked="" type="checkbox"/> (<i>this check-box may be marked only if the conditions for deposit accounts of the IPEA so permit</i>) is hereby authorized to charge any deficiency or credit any overpayment in the total fees indicated above to my deposit account.		
02-4800 Deposit Account Number	25 May 2000 Date (day/month/year)	<div style="text-align: center;">  Signature Peter K. Skiff </div> <div style="text-align: right;"> Registration No. 31,917 </div>

PATENT COOPERATION TREATY

PCT

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

REC'D 17 JAN 2001

WIPO

PCT

Applicant's or agent's file reference 021239-040	FOR FURTHER ACTION See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)	
International application No. PCT/US99/25427	International filing date (day/month/year) 29 OCTOBER 1999	Priority date (day/month/year) 29 OCTOBER 1998
International Patent Classification (IPC) or national classification and IPC IPC(7): A24B 15/28; A24B 15/18; A24B 15/00 and US Cl.: 131/332, 334, 331, 202		
Applicant PHILIP MORRIS (INCORPORATED) PRODUCTS INC.		

1.	This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.
2.	This REPORT consists of a total of <u>4</u> sheets.
<input type="checkbox"/>	This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority. (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).
	These annexes consist of a total of <u>0</u> sheets.
3.	This report contains indications relating to the following items:
I	<input checked="" type="checkbox"/> Basis of the report
II	<input type="checkbox"/> Priority
III	<input type="checkbox"/> Non-establishment of report with regard to novelty, inventive step or industrial applicability
IV	<input type="checkbox"/> Lack of unity of invention
V	<input checked="" type="checkbox"/> Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
VI	<input type="checkbox"/> Certain documents cited
VII	<input type="checkbox"/> Certain defects in the international application
VIII	<input type="checkbox"/> Certain observations on the international application

Date of submission of the demand 25 MAY 2000	Date of completion of this report 16 NOVEMBER 2000
Name and mailing address of the IPEA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231	Authorized officer DIONNE A. WALLS <i>Dionne A. Walls</i>
Facsimile No. (703) 305-3230	Telephone No. (703) 308-0661

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US99/25427

I. Basis of the report

1. With regard to the **elements** of the international application: *☒ the international application as originally filed☒ the description:

pages 1-30, as originally filed
pages NONE, filed with the demand
pages NONE, filed with the letter of

☒ the claims:

pages 31-37, as originally filed
pages NONE, as amended (together with any statement) under Article 19
pages NONE, filed with the demand
pages NONE, filed with the letter of

☒ the drawings:

pages 1-11, as originally filed
pages NONE, filed with the demand
pages NONE, filed with the letter of

☒ the sequence listing part of the description:

pages NONE, as originally filed
pages NONE, filed with the demand
pages NONE, filed with the letter of

2. With regard to the **language** all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.
These elements were available or furnished to this Authority in the following language which is:☐ the language of a translation furnished for the purposes of international search (under Rule 23.1(b)).☐ the language of publication of the international application (under Rule 48.3(b)).☐ the language of the translation furnished for the purposes of international preliminary examination (under Rules 55.2 and/or 55.3).3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:☐ contained in the international application in printed form.☐ filed together with the international application in computer readable form.☐ furnished subsequently to this Authority in written form.☐ furnished subsequently to this Authority in computer readable form.☐ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.☐ The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.4. ☒ The amendments have resulted in the cancellation of:☒ the description, pages NONE☒ the claims, Nos. NONE☒ the drawings, sheets/fig. NONE5. ☐ This report has been drawn as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the Supplemental Box (Rule 70.2(c)).**

* Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to this report since they do not contain amendments (Rules 70.16 and 70.17).

**Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report.

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US99/25427

V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. statement

Novelty (N)	Claims	<u>(Please See supplemental sheet)</u>	YES
	Claims	<u>(Please See supplemental sheet)</u>	NO
Inventive Step (IS)	Claims	<u>(Please See supplemental sheet)</u>	YES
	Claims	<u>(Please See supplemental sheet)</u>	NO
Industrial Applicability (IA)	Claims	<u>(Please See supplemental sheet)</u>	YES
	Claims	<u>(Please See supplemental sheet)</u>	NO

2. citations and explanations (Rule 70.7)

Claims 1-2, 5-6, 8, 21-22, 26, 28, 30, 34-35, 39-41, and 45 lack novelty under PCT Article 33(2) as being anticipated by Horsewell et al (US. Pat. No. 4,300,577).

Horsewell et al discloses all that is recited in these claims (Note: "second component/ion-exchange resin/polyethylene imine" corresponds to the claimed "reactive functional group"; "first component/e.g. silica gel" corresponds to the claimed "non-volatile inorganic substrate"; see col. 1, lines 4-6, 24-29, 34-37, 43-44, 57-64; col. 2, lines 12-13, 32-44, see abstract)

Claims 4 and 27 lack an inventive step under PCT Article 33(3) as being obvious over Horsewell et al (US. Pat. No. 4,300,577).

While Horsewell et al may not specifically disclose that a reagent is bonded to the filter fibers in an amount of 10-50% by weight, it would have been obvious to one having ordinary skill in the art at the time of the invention to incorporate the reagent onto the substrate at this percentage in order to ensure an adequate amount of reagent to effectuate the adequate and efficient removal of the gaseous component in the smoke.

Claims 7, 29, and 42 lack an inventive step under PCT Article 33(3) as being obvious over Horsewell et al (US. Pat. No. 4,300,577) in view of Keritsis (US. Pat. No. 5,115,823).

While Horsewell et al may not explicitly disclose that the reagent is incorporated in cigarette filter paper or polypropylene fibers, Keritsis teaches that most smoking filters are formed from materials, including paper and polystyrene, and that the particle-bearing filter of its invention can be made of such material. Therefore, it would have been obvious to one having ordinary skill in the art at the time of the invention to utilize paper or polypropylene fibers as the substrate upon which to carry the reagent because this is known in the art as taught by Keritsis (col. 2, lines 55-61; see fig. 1)
(Continued on Supplemental Sheet.)

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US99/25427

Supplemental Box

(To be used when the space in any of the preceding boxes is not sufficient)

Continuation of: Boxes I - VIII

Sheet 10

V. 1. REASONED STATEMENTS:

The report as to Novelty was positive (YES) with respect to claims 3-4, 7, 9-20, 23-25, 27, 29, 31-33, 36-38, 42-44 AND 46-47.

The report as to Novelty was negative (NO) with respect to claims 1-2, 5-6, 8, 21-22, 26, 28, 30, 34-35, 39-41 AND 45.

The report as to Inventive Step was positive (YES) with respect to claims 3, 10-20, 23-25, 32-33, 36-38, 43-44 AND 47.

The report as to Inventive Step was negative (NO) with respect to claims 1-2, 5-6, 8, 21-22, 26, 28, 30, 34-35, 39-41 AND 45.

The report as to Industrial Applicability was positive (YES) with respect to claims 1-47.

The report as to Industrial Applicability was negative (NO) with respect to claims NONE.

V. 2. REASONED STATEMENTS - CITATIONS AND EXPLANATIONS (Continued):

Claims 9, 31 and 46 lacks an inventive step under PCT Article 33(3) as being obvious over Horsewell et al (US. Pat. No. 4,300,577) in view of Gesser (US. Pat. No. 4,892,719).

While Horsewell et al may not disclose a replaceable filter element of an air ventilation system, Gesser discloses a device for removing aldehydes from indoor air, said device comprising a replaceable coated filter material (see col. 2, lines 15-26). therefore, it would have been obvious to one with ordinary skill in the art to utilize the filter of Horsewell et al as a filter element in an air ventilation system, as in Gesser, in order to appreciate the benefits of aldehyde removal in indoor air.

Claims 3, 10-20, 23-25, 32-33, 36-38, 43-44 and 47 meet the criteria set out in PCT Article 33(2)-(4), because the prior art does not teach or fairly suggest a filter comprising a reagent consisting of at least one reactive functional group being an aminopropylsilyl group and an amino-modified silica gel, as a substrate, said gel having a particle size of at least 10 microns or a mesh size of at least 60.

----- NEW CITATIONS -----

US 5,115,823 A (KERITSIS) 26 MAY 1992, see column 2, lines 55-61.

PCT REQUEST

021239-040

Original (for **SUBMISSION**) - printed on 29.10.1999 04:56:26 PM

0	For receiving Office use only	
0-1	International Application No.	
0-2	International Filing Date	
0-3	Name of receiving Office and "PCT International Application"	
0-4	Form - PCT/RO/101 PCT Request	
0-4-1	Prepared using	PCT-EASY Version 2.84 (updated 01.07.1999)
0-5	Petition The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	United States Patent and Trademark Office (USPTO) (RO/US)
0-7	Applicant's or agent's file reference	021239-040
I	Title of invention	FILTER FOR SELECTIVE REMOVAL OF A GASEOUS COMPONENT
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	all designated States except US
II-4	Name	PHILIP MORRIS INCORPORATED
II-5	Address:	120 Park Avenue New York, NY 10017 United States of America
II-6	State of nationality	US
II-7	State of residence	US
II-8	Telephone No.	(804) 274-5867
II-9	Facsimile No.	(804) 274-4778
III-1	Applicant and/or inventor	
III-1-1	This person is:	applicant and inventor
III-1-2	Applicant for	US only
III-1-4	Name (LAST, First)	KOLLER, Kent, B.
III-1-5	Address:	8401 Kintail Drive Chesterfield, VA 23838 United States of America
III-1-6	State of nationality	US
III-1-7	State of residence	US

PCT REQUEST

021239-040

Original (for SUBMISSION) - printed on 29.10.1999 04:56:26 PM

III-2	Applicant and/or inventor	
III-2-1	This person is:	applicant and inventor
III-2-2	Applicant for	US only
III-2-4	Name (LAST, First)	WRENN, Susan, E.
III-2-5	Address:	12130 Ivy Mill Road Chesterfield, VA 23832 United States of America
III-2-6	State of nationality	US
III-2-7	State of residence	US
III-3	Applicant and/or inventor	
III-3-1	This person is:	applicant and inventor
III-3-2	Applicant for	US only
III-3-4	Name (LAST, First)	HOUCK, Willie, G., Jr.
III-3-5	Address:	7753 Lake Forrest Drive Richmond, VA 23235 United States of America
III-3-6	State of nationality	US
III-3-7	State of residence	US
III-4	Applicant and/or inventor	
III-4-1	This person is:	applicant and inventor
III-4-2	Applicant for	US only
III-4-4	Name (LAST, First)	PAINE, John, B. III
III-4-5	Address:	13630 Trilithon Road Midlothian, VA 23235 United States of America
III-4-6	State of nationality	US
III-4-7	State of residence	US
IV-1	Agent or common representative; or address for correspondence The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name (LAST, First)	SKIFF, Peter, K.
IV-1-2	Address:	BURNS, DOANE, SWECKER & MATHIS, L.L.P. P.O. Box 1404 Alexandria, VA 22313-1404 United States of America
IV-1-3	Telephone No.	703-836-6620
IV-1-4	Facsimile No.	703-836-2021

PCT REQUEST

021239-040


Original (for SUBMISSION) - printed on 29.10.1999 04:56:26 PM

V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	<p>AP: GH GM KE LS MW SD SL SZ UG ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT</p> <p>EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT</p> <p>EP: AT BE CH&LI CY DE DK ES FI FR GB GR IE IT LU MC NL PT SE and any other State which is a Contracting State of the European Patent Convention and of the PCT</p> <p>OA: BF BJ CF CG CI CM GA GN GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT</p>
V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	<p>AE AL AM AT AU AZ BA BB BG BR BY CA CH&LI CN CR CU CZ DE DK DM EE ES FI GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MD MG MN MW MX NO NZ PL PT RO RU SD SE SG SI SK SL TJ TM TR TT TZ UA UG US UZ VN YU ZA ZW</p>
V-3	National Patent (States which have become party to the PCT after the issuance of this version of EASY)	MA Morocco
V-5	Precautionary Designation Statement In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.	
V-6	Exclusion(s) from precautionary designations	NONE
VI-1	Priority claim of earlier national application	
VI-1-1	Filing date	29 October 1998 (29.10.1998)
VI-1-2	Number	09/181,859
VI-1-3	Country	US
VI-2	Priority document request The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) identified above as item(s):	VI-1

PCT REQUEST

021239-040

Original (for SUBMISSION) - printed on 29.10.1999 04:56:26 PM

VII-1	International Searching Authority Chosen	United States Patent and Trademark Office (USPTO) (ISA/US)	
VIII	Check list	number of sheets	electronic file(s) attached
VIII-1	Request	4	-
VIII-2	Description	30	-
VIII-3	Claims	7	-
VIII-4	Abstract	1	abstract-040.txt
VIII-5	Drawings	11	-
VIII-7	TOTAL	53	
VIII-8	Accompanying items	paper document(s) attached	electronic file(s) attached
VIII-8	Fee calculation sheet	✓	-
VIII-10	Copy of general power of attorney	✓	-
VIII-16	PCT-EASY diskette	-	diskette
VIII-17	Other (specified):	Transmittal Sheet, Receipt Post Card and Check	-
VIII-18	Figure of the drawings which should accompany the abstract		
VIII-19	Language of filing of the international application	English	
IX-1	Signature of applicant or agent		
IX-1-1	Name (LAST, First)	SKIFF, Peter, K.	

FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	
10-2	Drawings:	
10-2-1	Received	
10-2-2	Not received	
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application	
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)	
10-5	International Searching Authority	ISA/US
10-6	Transmittal of search copy delayed until search fee is paid	

FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--

PCT (ANNEX - FEE CALCULATION SHEET)

021239-040

Original (for SUBMISSION) - printed on 29.10.1999 04:56:26 PM


(This sheet is not part of and does not count as a sheet of the international application)

0	For receiving Office use only	
0-1	International Application No.	
0-2	Date stamp of the receiving Office	
0-4	Form - PCT/RO/101 (Annex)	
0-4-1	PCT Fee Calculation Sheet Prepared using	PCT-EASY Version 2.84 (updated 01.07.1999)
0-9	Applicant's or agent's file reference	021239-040
2	Applicant	PHILIP MORRIS INCORPORATED, et al.
12	Calculation of prescribed fees	fee amount/multiplier total amounts (USD)
12-1	Transmittal fee T	⇒ 240
12-2	Search fee S	⇒ 450
12-3	International fee Basic fee (first 30 sheets) b1	455
12-4	Remaining sheets	23
12-5	Additional amount (X)	10
12-6	Total additional amount b2	230
12-7	b1 + b2 = B	685
12-8	Designation fees Number of designations contained in international application	83
12-9	Number of designation fees payable (maximum 10)	10
12-10	Amount of designation fee (X)	105
12-11	Total designation fees D	1,050
12-12	PCT-EASY fee reduction R	-140
12-13	Total International fee (B+D-R) I	⇒ 1,595
12-14	Fee for priority document Number of priority documents requested	1
12-15	Fee per document (X)	15
12-16	Total priority document fee P	⇒ 15
12-17	TOTAL FEES PAYABLE (T+S+I+P)	⇒ 2,300
12-19	Mode of payment	authorization to charge deposit account
12-20	Deposit account instructions The receiving Office:	United States Patent and Trademark Office (USPTO) (RO/US)
12-20-1	is hereby authorized to charge the total fees indicated above to my deposit account	✓
12-20-2	is hereby authorized to charge any deficiency or credit any over-payment in the total fees indicated above to my deposit account	✓
12-21	Deposit account No.	02-4800
12-22	Date	29 October 1999 (29.10.1999)

PCT (ANNEX - FEE CALCULATION SHEET)

021239-040

Original (for SUBMISSION) - printed on 29.10.1999 04:56:26 PM

12-23	Name and signature	SKIFF, Peter, K. 
-------	--------------------	--

VALIDATION LOG AND REMARKS

13-2-2	Validation messages States	Yellow! Additional national designation added: Obtain updated maintenance tables rather than using this field.
13-2-6	Validation messages Contents	Green? Figure of the drawings which should accompany the abstract not specified. Please verify.
		Green? Reference number for attached copy of general power of attorney not indicated.
13-2-7	Validation messages Fees	Green? Please confirm that fee schedule utilized is the latest available
13-2-8	Validation messages Payment	Green? Please ensure that you have a valid deposit account with the receiving Office selected.

PCTWORLD INTELLECTUAL PROPERTY ORGANIZATION
International Bureau

INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification ⁷ : A24B 15/28, 15/18, 15/00		A1	(11) International Publication Number: WO 00/25610
			(43) International Publication Date: 11 May 2000 (11.05.00)
(21) International Application Number: PCT/US99/25427		(81) Designated States: AE, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CR, CU, CZ, DE, DK, DM, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).	
(22) International Filing Date: 29 October 1999 (29.10.99)			
(30) Priority Data: 09/181,859 29 October 1998 (29.10.98) US			
(71) Applicant (for all designated States except US): PHILIP MORRIS INCORPORATED [US/US]; 120 Park Avenue, New York, NY 10017 (US). <i>29 Apr 01/30 mos</i>			
(72) Inventors; and (73) Inventors/Applicants (for US only): ✓ KOLLER, Kent, B. [US/US]; 8401 Kintail Drive, Chesterfield, VA 23838 (US); WRENN, Susan, E. [US/US]; 12130 Ivy Mill Road, Chesterfield, VA 23832 (US); HUCK, Willie, G., Jr. [US/US]; 7753 Lake Forrest Drive, Richmond, VA 23235 (US); PAINE, John, B., III [US/US]; 13630 Trilithon Road, Midlothian, VA 23235 (US).		Published <i>With international search report.</i>	
(74) Agent: SKIFF, Peter, K.; Burns, Doane, Swecker & Mathis, L.L.P., P.O. Box 1404, Alexandria, VA 22313-1404 (US).			
(54) Title: FILTER FOR SELECTIVE REMOVAL OF A GASEOUS COMPONENT			
(57) Abstract <p>A filter such as an air having a reagent which chemically reacts with and removes a gaseous component of an air stream. The reagent contains functional groups covalently bonded to a non-volatile inorganic substrate which is incorporated in the filter. The filter can remove gaseous components such as aldehydes. Preferred functional groups are 3-aminopropylsilyl groups covalently bonded to silica gel (APS silica gel). The reagent can be contained in a space in the filter or incorporated in one or more filter elements. The reagent can be part of or coated on paper such as filter paper or incorporated in non-paper filter elements formed from fibrous materials such as cellulose acetate or polypropylene fibers. Other preferred reagents include aminoethylaminopropylsilyl silica gel (AEAPS) and aminoethylaminoethylaminopropylsilyl silica gel (AEAEAPS).</p>			

FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
AU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav Republic of Macedonia	TM	Turkmenistan
BF	Burkina Faso	GR	Greece			TR	Turkey
BG	Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MN	Mongolia	UA	Ukraine
BR	Brazil	IL	Israel	MR	Mauritania	UG	Uganda
BY	Belarus	IS	Iceland	MW	Malawi	US	United States of America
CA	Canada	IT	Italy	MX	Mexico	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NE	Niger	VN	Viet Nam
CG	Congo	KE	Kenya	NL	Netherlands	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NO	Norway	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's Republic of Korea	NZ	New Zealand		
CM	Cameroon		Republic of Korea	PL	Poland		
CN	China	KR	Republic of Korea	PT	Portugal		
CU	Cuba	KZ	Kazakstan	RO	Romania		
CZ	Czech Republic	LC	Saint Lucia	RU	Russian Federation		
DE	Germany	LI	Licchtenstein	SD	Sudan		
DK	Denmark	LK	Sri Lanka	SE	Sweden		
EE	Estonia	LR	Liberia	SG	Singapore		

FILTER FOR SELECTIVE REMOVAL OF A GASEOUS COMPONENT

BACKGROUND OF THE INVENTION

1. Field of the Invention

This invention generally relates to a filter such as air filter. More particularly, the invention relates to a filter that can selectively remove a gaseous component such as aldehydes from a gas mixture, a method of making the filter and a method of removing a gaseous component from a gas mixture.

2. Description of the Related Art

A wide variety of materials have been suggested in the art as filters for tobacco smoke. Such filter materials include cotton, paper, cellulose, and certain synthetic fibers. These filter materials, however, only remove particulates and condensable components from tobacco smoke. They have little or no effect in removing certain gaseous components, e.g., aldehydes, from tobacco smoke.

In light of this, a number of additives have been proposed in the art to supplement the performance of the filter materials. Exemplary additives are mentioned in, for example, U.S. Patent Nos. 2,815,761; 2,881,772; 2,968,306; 3,003,504; and 3,354,886. Some of the additives known in the art are effective in removing certain amounts of gaseous components from tobacco smoke. However, those additives also suffer from various drawbacks.

For example, U.S. Patent No. 2,968,306 discloses the use of certain amino acids, such as glycine, for removing aldehydes in tobacco smoke. It has been discovered that while glycine can reduce the level of formaldehyde in tobacco smoke, it is not stable in the cigarette filter manufacturing process. Moreover, it releases ammonia odor during storage.

-2-

U.S. Patent Nos. 4,604,110 and 4,534,775 disclose an air treatment filter element for removing odors from indoor air. The '110 and '775 patents disclose that the filter element is produced by contacting an adsorbent material such as zeolite, activated carbon and/or silica gel with a liquid for inhibiting growth of microorganisms.

U.S. Patent No. 4,892,719 discloses a furnace filter for removal of indoor pollutants such as formaldehyde or acidic gases such as SO_2 , SO_3 , NO_x and H_2S . The filter includes a polymeric coating with functional groups such as polyallylamine or polyvinylamine for reacting with formaldehyde or acrolein.

U.S. Patent Nos. 4,227,904; 4,374,814; 4,547,350; and 4,724,242 disclose filter arrangements for purifying air. The '904 patent discloses a gas phase permeable filter for home applications such as ductless range hoods, room air purifiers, electronic air cleaners, air conditioners, and heating/ventilating systems and for commercial/industrial applications where fuel exhaust and/or manufacturing operations generate odorants such as sulfur dioxide, formaldehyde, phenols, etc. The odor removing filter can be incorporated in a filter arrangement which also removes smoke, dust, or other particulates. The odor removing material can be flakes, particles, pellets or granules and the filter material can be activated carbon flakes or granules or other substance such as impregnated activated alumina, both of which are adhesively bonded to a porous substrate. A filter is assembled by providing a U-shaped frame around the edges of two such substrates with the bonded particles facing each other. The '350 patent discloses an air filter such as fiberglass or open cell polyurethane which includes a thin layer of polymeric amine such as polyethylenimine, the coating being effective to react with aldehydes and acidic gases. The '242 patent discloses an open-celled foamed gypsum and carbonaceous material for absorbing gases such as carbon monoxide, sulfur dioxide, ozone, ammonia, nitrogen oxides and formaldehyde, the filter material being used as absorbent particles in diapers and undergarments. The '814 patent discloses a filter for removing formaldehyde with a solid shaped

-3-

composition prepared by coating a solid substrate or impregnating a porous or fibrous substrate with a composition including one or more polyhydric water-soluble polymers and water.

While various filter arrangements have been proposed for the removal of pollutants, it is an object of the present invention to provide an improved air filter that can selectively remove aldehydes from ambient air.

Thus, it is an object of the present invention to provide a filter arrangement and, more particularly, an air filter that can selectively remove a gaseous component such as aldehydes from a gas mixture.

10

SUMMARY OF THE INVENTION

15

The invention provides a filter such as an air filter which incorporates a reagent comprising at least one reactive functional group covalently bonded to a non-volatile inorganic substrate for selective removal of a gaseous component such as an aldehyde from a gas mixture such as ambient air. The reagent is preferably incorporated in a filter element exposed to the gas mixture such that the reactive functional group chemically reacts with aldehyde and removes it from the gas mixture.

20

It has been surprisingly discovered that a reagent comprising at least one reactive functional group covalently bonded to a non-volatile inorganic substrate is selective in removing a gaseous component such as aldehydes from a gas mixture such as ambient air. According to a preferred embodiment, the reagent can be incorporated in an air filter wherein the reactive functional group chemically reacts with a gaseous component of an air stream to remove it from the air stream.

25

The preferred functional group is an aminopropylsilyl group such as a 3-aminopropylsilyl group. The preferred substrate is in particle form, and more preferably is silica gel. The most preferred functional group/substrate arrangement (reagent) contains 3-aminopropylsilyl groups bonded to silica gel (hereinafter referred to as "APS silica gel"). This reagent can selectively remove

-4-

gaseous components such as polar compounds (e.g., aldehydes and hydrogen cyanide) from gas mixtures such as ambient air. Other preferred reagents include aminoethylaminopropylsilyl (AEAPS) silica gel and aminoethylaminoethylaminopropylsilyl (AEAEAPS) silica gel.

5

BRIEF DESCRIPTION OF THE DRAWINGS

Figure 1 is a perspective partially exploded view of a cigarette constructed in accordance with one embodiment of the present invention wherein folded paper containing a reagent which chemically reacts with a component of cigarette smoke is inserted into a hollow portion of a tubular filter element of the cigarette;

10

Figure 2 is a perspective partially exploded view of another embodiment of the present invention wherein the reagent is incorporated in folded paper inserted into a hollow portion of a tubular filter element;

15

Figure 3 is a perspective partially exploded view of another embodiment of the present invention wherein the reagent is incorporated in a plug-space-plug filter element;

Figure 4 is a perspective partially exploded view of another embodiment of the present invention wherein the reagent is incorporated in a three-piece filter element having three plugs;

20

Figure 5 is a perspective partially exploded view of another embodiment of the present invention wherein the reagent is incorporated in a four-piece filter element having a plug-space-plug arrangement and a hollow sleeve;

Figure 6 is a perspective partially exploded view of another embodiment of the present invention wherein the reagent is incorporated in a three-part filter element having two plugs and a hollow sleeve;

25

Figure 7 is a perspective partially exploded view of another embodiment of the present invention wherein the reagent is incorporated in a two-part filter element having two plugs;

-5-

Figure 8 is a perspective partially exploded view of another embodiment of the present invention wherein the reagent is incorporated in a filter element of a cigarette used with an electrical smoking device;

5 Figure 9 depicts the chemical structures of the starting materials, the intermediate products, and the final APS silica gel reagent of a representative process for preparing the reagent used in the invention;

Figure 10 shows a graphic representation of silica gel wherein the typical Si-O-Si bond angle is 145° , the Si-O bond length is about 1.62 Å and the typical Si-Si distance is about 3.06Å;

10 Figure 11 shows a graphic representation of APS silica gel wherein the typical Si-O-Si bond angle is 145° , the Si-O bond length is about 1.62 Å and the typical Si-Si distance is about 3.06Å;

Figure 12 depicts AEAPS silica gel and its silane precursor;

Figure 13 depicts AEAEAPS silica gel and its silane precursor;

15 Figure 14 shows a chemical formula representation of how the formaldehyde can be chemically bonded to the APS silica gel when cigarette smoke comes into contact with the APS silica gel;

Figure 15 shows an air filter in accordance with the invention which includes amino-modified silica gel for removing aldehydes from ambient air;

20 Figure 16 shows a schematic of a process line for incorporating the amino-modified silica gel into fibrous material which can be used for a filter in accordance with the invention; and

Figure 17 is a graph showing results of tests wherein various types of amino-modified silica gel were used to remove formaldehyde from a gas stream.

25 DETAILED DESCRIPTION OF THE INVENTION

The invention provides a filter arrangement which is effective in removing a component of a gas mixture such as an air stream containing cigarette smoke or ambient air by chemically reacting a reagent with the gaseous component. The

-6-

reagent preferably comprises at least one reactive functional group. In order to prevent the reagent or its reaction product with the targeted gaseous component from being carried back into the gas mixture, the functional group is covalently bonded to an inorganic non-volatile substrate. Such an arrangement is
5 advantageous over filter arrangements wherein gaseous components are absorbed, adsorbed, or otherwise non-chemically removed from a gas mixture. Such non-chemically removed components may be removed only temporarily and could reenter a gas mixture such as an air stream or if reacted with a volatile reagent, provide products that are themselves volatile and hence could reenter the gas
10 mixture. According to the present invention, because the reactive functional group is covalently bonded to the substrate, once the gaseous component chemically reacts with the reagent, the removed component (and its reaction products) can be prevented from reentering the gas mixture.

The invention is first explained in connection with a cigarette filter. In the
15 most preferred embodiment, the reagent is an amino-modified silica gel such as APS silica gel. However, any suitable amino-modified silica gel can be used in accordance with the invention. Without wishing to be bound by theory, it is believed that the APS silica gel contains primary amine groups. Under ordinary smoking conditions, the primary amine groups chemically react with and
20 covalently bond to the aldehydes in tobacco smoke. The aldehydes are thus selectively removed from the tobacco smoke. Further, since the reactive functional groups and their resulting products from reaction with aldehydes are covalently bonded to the silica gel which is non-volatile, the mainstream tobacco smoke is essentially free of APS silica gel as well as the aldehydes which are
25 bonded thereto.

Aldehydes in tobacco smoke that can be selectively removed by the reagent of the invention include, but are not limited to formaldehyde, acetaldehyde, acrolein, malonaldehyde, crotonaldehyde, etc.

-7-

In a first preferred embodiment, the reagent such as APS silica gel is incorporated into or onto a support such as paper (e.g., tipping paper) that is located along a filter portion of a cigarette. As will be recognized by persons skilled in the art, such paper can be used, for example, as a wrapper or a liner in the filter portion of the cigarette. The reagent such as APS silica gel can also be loaded onto a support such as lightly or tightly folded paper inserted into a hollow portion of the cigarette filter. The support is preferably in the form of a sheet material such as crepe paper, filter paper, or tipping paper. However, other suitable support materials such as organic or inorganic cigarette compatible materials can also be used.

Figure 1 illustrates a cigarette 2 having a tobacco rod 4, a filter portion 6, and a mouthpiece filter plug 8. As shown, the APS silica gel reagent can be loaded onto folded paper 10 inserted into a hollow cavity such as the interior of a free-flow sleeve 12 forming part of the filter portion 6.

Figure 2 shows a cigarette 2 having a tobacco rod 4 and a filter portion 6, wherein the folded paper 10 is located in the hollow cavity of a first free-flow sleeve 13 located between the mouthpiece filter 8 and a second free-flow sleeve 15. The paper 10 can be used in forms other than as a folded sheet. For instance, the paper 10 can be deployed as one or more individual strips, a wound roll, etc. In whichever form, a desired amount of reagent such as APS silica gel can be provided in the cigarette filter portion by a combination of the coated amount of reagent/area of the paper and/or the total area of coated paper employed in the filter (e.g., higher amounts of APS silica gel can be provided simply by using larger pieces of coated paper). In the cigarettes shown in Figures 1 and 2, the tobacco rod 4 and the filter portion 6 are joined together with tipping paper 14. In both cigarettes, the filter portion 6 may be held together by filter overwrap 11.

The reagent such as APS silica gel can be incorporated into the filter paper in a number of ways. For example, the APS silica gel can be mixed with water to form a slurry. The slurry can then be coated onto pre-formed filter paper and

-8-

allowed to dry. The filter paper can then be incorporated into the filter portion of a cigarette in the manner shown in Figures 1 and 2. Alternatively, the dried paper can be wrapped into a plug shape and inserted into a filter portion of the cigarette. For example, the paper can be wrapped into a plug shape and inserted as a plug
5 into the interior of a free-flow filter element such as a polypropylene or cellulose acetate sleeve. In another arrangement, the paper can comprise an inner liner of such a free-flow filter element.

Alternatively and more preferably, the reagent such as APS silica gel is added to the filter paper during the paper-making process. For example, the APS
10 silica gel can be mixed with bulk cellulose to form a cellulose pulp mixture. The mixture can be then formed into filter paper according to methods known in the art.

In another preferred embodiment of the present invention, the reagent such as APS silica gel is incorporated into the fibrous material of the cigarette filter
15 portion itself. Such filter materials include, but are not limited to, fibrous filter materials including paper, cellulose acetate fibers, and polypropylene fibers. This embodiment is illustrated in Figure 3, which shows a cigarette 2 comprised of a tobacco rod 4 and a filter portion 6 in the form of a plug-space-plug filter having a mouthpiece filter 8, a plug 16, and a space 18. The plug 16 can comprise a tube
20 or solid piece of material such as polypropylene or cellulose acetate fibers. The tobacco rod 4 and the filter portion 6 are joined together with tipping paper 14. The filter portion 6 may include a filter overwrap 11. The filter overwrap 11 contains traditional fibrous filter material and reagent such as APS silica gel can be incorporated in or on the filter overwrap 11 such as by being coated thereon.
25 Alternatively, the APS silica gel can be incorporated in the mouthpiece filter 8, in the plug 16, and/or in the space 18. Moreover, the APS silica gel can be incorporated in any element of the filter portion of a cigarette. For example, the filter portion may consist only of the mouthpiece filter 8 and the APS silica gel can be incorporated in the mouthpiece filter 8 and/or in the tipping paper 14.

-9-

Figure 4 shows a cigarette 2 comprised of a tobacco rod 4 and filter portion 6. This arrangement is similar to that of Figure 3 except the space 18 is filled with granules of APS silica gel or a plug 15 made of material such as fibrous polypropylene or cellulose acetate containing APS silica gel. As in the previous embodiment, the plug 16 can be hollow or solid and the tobacco rod 4 and filter portion 6 are joined together with tipping paper 14. There is also a filter overwrap 11.

Figure 5 shows a cigarette 2 comprised of a tobacco rod 4 and a filter portion 6 wherein the filter portion 6 includes a mouthpiece filter 8, a filter overwrap 11, tipping paper 14 to join the tobacco rod 4 and filter portion 6, a space 18, a plug 16, and a hollow sleeve 20. The APS silica gel can be incorporated into one or more elements of the filter portion 6. For instance, the APS silica gel can be incorporated into the sleeve 20 or granules of the APS silica gel can be filled into the space within the sleeve 20. If desired, the plug 16 and sleeve 20 can be made of material such as fibrous polypropylene or cellulose acetate containing APS silica gel. As in the previous embodiment, the plug 16 can be hollow or solid.

Figures 6 and 7 show further modifications of the filter portion 6. In Figure 6, cigarette 2 is comprised of a tobacco rod 4 and filter portion 6. The filter portion 6 includes a mouthpiece filter 8, a filter overwrap 11, a plug 22, and a sleeve 20, and the APS silica gel can be incorporated in one or more of these filter elements. In Figure 7, the filter portion 6 includes a mouthpiece filter 8 and a plug 24, and the APS silica gel can be incorporated in one or more of these filter elements. Like the plug 16, the plugs 22 and 24 can be solid or hollow. In the cigarettes shown in Figures 6 and 7, the tobacco rod 4 and filter portion 6 are joined together by tipping paper 14.

Various techniques can be used to apply the reagent such as APS silica gel to filter fibers or other substrate supports. For example, the APS silica gel can be added to the filter fibers before they are formed into a filter cartridge, e.g., a tip

-10-

for a cigarette. The APS silica gel can be added to the filter fibers, for example, in the form of a dry powder or a slurry by methods known in the art. If the APS silica gel is applied in the form of a slurry, the fibers are allowed to dry before they are formed into a filter cartridge.

5 In another preferred embodiment, the reagent such as APS silica gel is employed in a hollow portion of a cigarette filter. For example, some cigarette filters have a plug/space/plug configuration in which the plugs comprise a fibrous filter material and the space is simply a void between the two filter plugs. That void can be filled with the APS silica gel of the present invention. An example of
10 this embodiment is shown in Figure 3. The APS silica gel can be in granular form or can be loaded onto a suitable support such as a fiber or thread.

 In another embodiment of the present invention, the reagent such as APS silica gel is employed in a filter portion of a cigarette for use with a smoking device as described in U.S. Patent No. 5,692,525, the entire content of which is
15 hereby incorporated by reference. Figure 8 illustrates one type of construction of a cigarette 100 which can be used with an electrical smoking device. As shown, the cigarette 100 includes a tobacco rod 60 and a filter portion 62 joined by tipping paper 64. The filter portion 62 preferably contains a tubular free-flow filter element 102 and a mouthpiece filter plug 104. The free-flow filter element
20 102 and mouthpiece filter plug 104 may be joined together as a combined plug 110 with plug wrap 112. The tobacco rod 60 can have various forms incorporating one or more of the following items: an overwrap 71, another tubular free-flow filter element 74, a cylindrical tobacco plug 80 preferably wrapped in a plug wrap 84, a tobacco web 66 comprising a base web 68 and tobacco flavor
25 material 70, and a void space 91. The free-flow filter element 74 provides structural definition and support at the tipped end 72 of the tobacco rod 60. At the free end 78 of the tobacco rod 60, the tobacco web 66 together with overwrap 71 are wrapped about cylindrical tobacco plug 80. Various modifications can be

-11-

made to a filter arrangement for such a cigarette incorporating the reagent of the invention.

In such a cigarette, the reagent such as APS silica gel can be incorporated in various ways such as by being loaded onto paper or other substrate material which is fitted into the passageway of the tubular free-flow filter element 102 therein. It may also be deployed as a liner or a plug in the interior of the tubular free-flow filter element 102. Alternatively, the reagent such as APS silica gel can be incorporated into the fibrous wall portions of the tubular free-flow filter element 102 itself. For instance, the tubular free-flow filter element or sleeve 102 can be made of suitable materials such as polypropylene or cellulose acetate fibers and the reagent such as APS silica gel can be mixed with such fibers prior to or as part of the sleeve forming process.

In another embodiment, the reagent such as APS silica gel can be incorporated into the mouthpiece filter plug 104 instead of in the element 102. However, as in the previously described embodiments, according to the invention, the reagent such as APS silica gel may be incorporated into more than one component of a filter portion such as by being incorporated into the mouthpiece filter plug 104 and into the tubular free-flow filter element 102.

The filter portion 62 of Figure 8 can also be modified to create a void space into which the reagent such as granular APS silica gel can be inserted.

As explained above, the APS silica gel can be incorporated in various support materials. When the APS silica gel is used in filter paper, the silica gel beads or particles may have an average particle diameter of 10 to 100 μm , preferably 40 to 50 μm . When the APS silica gel is used in filter fibers or other mechanical supports, larger silica gel particles may be used. Such particles preferably have a mesh size from 14 to 60, and more preferably from 35 to 60 mesh. The silica gel particles preferably have an average pore size of about 40 to about 250 \AA , and more preferably, about 150 \AA .

-12-

The amount of APS silica gel employed in the cigarette filter by way of incorporation on a suitable support such as filter paper and/or filter fibers depends on the amount of aldehydes in the tobacco smoke and the amount of aldehydes desired to be removed. As an example, the filter paper and the filter fibers may
5 contain from 10% to 50% by weight of the APS silica gel.

Any commercially available APS silica gel such as that available from J.T. Baker Chemical Co., Philipsburg, New Jersey, can be used in the present invention. It should be noted that the J.T. Baker product is "capped." This means that the free silica gel surface, i.e., the surface that has not been covalently
10 bonded to the APS silica gel groups, is made to be non-polar by coverage with hydrophobic groups.

The APS silica gel can also be made, for example, by mixing aminopropyltriethoxysilane, more preferably 3-aminopropyltriethoxysilane, with silica gel in a water and ethanol solvent. Other solvents, such as toluene, can also
15 be used. The mixture is heated for several hours to allow the 3-aminopropyltriethoxysilane to react with and chemically bond to the silica gel surface. The reaction mixture is then decanted to obtain a reaction product comprising the APS silica gel. The reaction product is subsequently rinsed with a solvent, and dried in an oven at an elevated temperature such as around 100°C or
20 above. Although the rinsing and drying steps are optional, the drying step is preferred. Unlike the J.T. Baker product, the APS silica gel made by this method is not "capped."

The above paragraph describes a process routine which may be practiced with other aminopropyltrialkoxysilanes, such as 3-aminopropyltrimethoxysilane.

25 The APS silica gel can also be prepared by the following more specific procedure. A suspension of the chosen silica gel is rapidly stirred in a solution of water and ethanol. To that mixture is added a 3-aminopropyltrialkoxysilane compound, preferably 3-aminopropyltriethoxysilane. The 3-aminopropyltrialkoxysilane can be added before, during, or after heating. The

-13-

3-aminopropyltrialkoxysilane is preferably pre-diluted with anhydrous ethanol.

The resulting mixture is then heated, preferably to the boiling point. In the most preferred embodiments, the ethanol is distilled off and replaced with water. The solids are isolated by a procedure such as filtration and with an optional solvent
5 rinse, preferably water. The solids are then heated in an oven until water loss has proceeded to equilibrium with the surroundings. Typical embodiments entail heating overnight at about 105°C.

Figure 9 depicts the most likely mechanism of the reaction that occurs in the making of APS silica gel when 3-aminopropyltriethoxysilane and silica gel are
10 used as the starting materials. This mechanism is also applicable to other 3-aminopropyltrialkoxysilanes. As shown, when 3-aminopropyltriethoxysilane is contacted with water under appropriate conditions, the ethoxy groups are replaced with hydroxyl so that a 3-aminopropyltrihydroxysilane intermediate is obtained. That intermediate is also believed to undergo a conformational change (which
15 stabilizes the monomeric form sufficiently to allow it to be used in aqueous medium) before reacting with the silica gel, as shown in Figure 9. Figure 9 further shows the structure of the intermediate reaction product of 3-aminopropyltrihydroxysilane and silica gel. Figure 9 finally shows the cross-linked APS silica gel product after curing. The curing causes the loss of
20 hydroxyl groups to result in at least a doubly linked silicon anchor for the reactive group.

As shown in Figure 9, each silicon atom of silica gel is tetrahedrally coordinated by four oxygen atoms, which are either singly bonded to two silicon atoms or to a silicon and a proton (OH). The size of the pore (represented in
25 Figure 9 as a ring) can vary, but is typically about 150Å in diameter.

The 3-aminopropyltriethoxysilane can be obtained commercially from Dow Corning Corp. The silica gel can be obtained commercially from the Grace Davison Division of W.R. Grace & Co.

EXPERIMENTAL EXAMPLES

-14-

Preparation of APS Silica Gel Material

Grace Davison 646 (35 X 60 Mesh, 150-angstrom pore size) Silica Gel (circa 1700 to 2000 grams) was placed into a 12-liter Pyrex glass kettle. Distilled water (4 liters) and 95% ethanol (2 liters; 100% ethanol is also acceptable) was added. A clamp-on head had a central neck for the stirring-rod, and three peripheral necks for reagent addition and vapor exit. A stainless steel paddle stirrer was attached to a high-torque (50 inch-pound) digitally controlled stirrer. The high torque stirrer needed to be double-clamped to a sturdy rack system, and served as the point of reference with respect to the kettle. The latter was raised and lowered by a system of "Lab-Jacks," and positioned precisely with respect to the fixed stirrer-rod. The stirrer blade needs to be fairly close to the kettle bottom, but not touching. The blade must never touch the bottom even during "bumping" induced rebound of the flask/kettle. The flask needs to be restrained to prevent motion during "bumping," which is unavoidable, but which the stirring minimizes. A plastic bearing was found to be advantageous since stainless steel bearings were found to be prone to seizing up, and glass bearings were prone to breakage. The mixture was stirred at 200 to 300 RPM, and heated (12 liter mantle, dual heating zone, 100 volts each zone). 3-aminopropyltriethoxysilane (1 x 500 gram bottle), diluted with 100% ethanol (1 liter, including the rinsings) was added as quickly as possible to the stirred heated mixture. (Higher levels of APS functional group incorporation could be achieved by increasing the amount of reagent used).

The ethanol was distilled off. When about 2 liters of aqueous ethanol distillate had collected, water (2 liters) was added to the reaction to restore the original volume. Two more liters of distillate were collected, and two more liters of replacement water were added. The heating was shut off, and stirring was continued until bumping ceased. The mixture was left to cool overnight. The apparatus was dismantled, and the silica was swirled manually and dumped into 4 liter plastic beakers, using recycled supernatant liquid to complete the removal of

-15-

solids. The solids were filtered off onto large (18 to 24 cm diameter) Buchner funnels, with minimal water rinsing (a few hundred milliliters at most). After suction had removed most of the liquid, the moist solids were transferred to stainless steel trays, to dry overnight at 105°C in an oven.

5 Depending on the amount of 3-aminopropyltriethoxysilane employed, relative to the starting silica gel, the dried products showed nominal weight gains ranging from about 8% to about 24%. One of the batches used in the examples below was prepared from 1692.4 grams of Grace Division Silica Gel 646 and 500.1 grams of 3-aminopropyltriethoxysilane under the general conditions described
10 above. After drying, 1891 grams of APS silica was obtained. A sample was analyzed for C, H, and N. Found: C, 4.21%, H, 1.37%, N, 1.58%. Based on the nitrogen analysis, the 3-aminopropyl content of the silica was 6.55% by weight of product total.

Cigarette Testing

15 Several tests were conducted to determine the ability of the cigarette filter of the present invention to remove aldehydes from tobacco smoke as compared to conventional devices. The tests measured the amount of aldehydes removed from the wholestream smoke after the cigarette was fully smoked. WS represents the amount, in %, of aldehydes removed from the wholestream smoke after all the
20 smoke has been collected and analyzed. TPM represents the amount, in mg/cigarette, of particulate material collected in the filter portion of the cigarette.

 In the following tests, the silica gels used showed a nominal weight gain of about 8 to 25% from the original silica gel during the manufacturing process outlined above. Based on the tests below, a preferred weight gain is around 8 to
25 16, preferably 10 to 15 wt. %. It is important to note that this weight gain does not refer to weight gain as a result of removing aldehydes. It refers to weight gain from the reaction that adds functional groups such as APS functional groups to the silica gel. APS silica gels that are especially effective when employed in accordance with this invention exhibit a nitrogen content preferably in the range of

-16-

about 1 to 3 percent by weight, and more preferably in the range of about 1.5 to about 2.1 percent.

Example 1

Filter sections of cigarettes were constructed in accordance with Figure 1 and with the tobacco rod section of Figure 8. A filter section constructed in accordance with the invention identified as Sample 2 contained 16.5 mg of APS silica gel on a folded piece of filter paper 10 (17 mm x 23 mm) inserted in the hollow portion of the tubular filter 12. Another filter section constructed in accordance with the invention identified as Sample 3 contained 21 mg of APS silica gel on a folded piece of filter paper 10 (22 mm x 23 mm) inserted into the hollow portion of the tubular filter 12. A comparative filter section using a folded piece of the filter paper (17 mm x 23 mm) paper (without any APS silica gel) fitted into the hollow portion of the tubular filter was constructed as a control and identified as Sample 1. For Samples 2 and 3, 15 cigarettes were made for TPM measurements and 9 were made for WS measurements. For control Sample 1, 15 cigarettes were made for TPM measurements and 15 for WS measurements. The results are shown in Table 1 below.

Table 1

SAMPLE	TPM	WS
1 Control	2.85	
2 16.5 mg reagent	2.83	~ 61 %
3 21.0 mg reagent	3.11	~ 78 %

Example 2

Cigarettes similar to those tested in Example 1 included a shorter section containing the APS silica gel. In Samples 1-3, the filter section was constructed in accordance with Figure 2 and included a 16 mm sleeve 13, a 7 mm sleeve 12,

-17-

and a 7 mm filter plug 8. The sleeve 12 contained a folded sheet (7 mm x 75 mm) of APS silica gel coated or uncoated paper. Three samples identified as control Sample 1 (uncoated paper), Sample 2 (paper coated with 11 mg APS silica gel), and Sample 3 (paper coated with 22 mg APS silica gel) were tested. 15 cigarettes of each sample were made for TPM measurement and 9 for WS measurement. The results are shown in Table 2 below.

Table 2

SAMPLE	TPM	WS
1 (Control)	3.37	
2 11 mg reagent	3.14	~ 69%
3 22 mg reagent	2.35	~ 78%

Example 3

Cigarettes were constructed in accordance with a more conventional cigarette having a tobacco rod like that shown in Figure 2 and a conventional filter element. Sample 1 is a control sample without APS silica gel and Sample 2 contained 50 mg APS silica gel in the filter element. The WS was measured for each and the results are shown in Table 3.

Table 3

Sample	WS
1 Control	
2 50 mg reagent	~ 71%

-18-

Example 4

Cigarettes were constructed in accordance with Figure 8 having APS silica gel contained in the mouthpiece filter. Sample 1 is a control sample which did not include APS silica gel and Samples 2 and 3 contained APS silica gel in the mouthpiece filter 104 which was 7 mm long. The samples also included a sleeve 102 adjacent the mouthpiece filter which was 23 mm long and constructed of polypropylene. In Sample 3, 11 mg APS silica gel was included in an additional polypropylene sleeve 74 having a length of 7 mm and located in the tobacco rod at an end thereof adjacent the filter element. The WS was measured for each and the results are shown in Table 4.

Table 4

	SAMPLE	WS
1	Control	
2	Polypropylene mouthpiece filter with 12 mg reagent	~ 46%
3	Polypropylene mouthpiece filter with 11 mg reagent	~ 41%

15

Example 5

Cigarettes were constructed in accordance with Figure 8 having APS silica gel contained in various filter elements. The cigarettes were tested for WS and TPM levels and the results are shown in Table 5 below.

Table 5

	SAMPLE	TPM	WS
1	Control		
2	Polypropylene sleeve 102 with 40 mg reagent and second polypropylene sleeve 74 with 11 mg reagent	5.88	~ 38%
3	Polypropylene sleeve 102 with 40 mg reagent	5.11	~ 35%

20

-19-

4	Cellulose acetate sleeve 102 with 50 mg reagent	4.71	~ 35%
5	Polypropylene sleeve 102 with 25 mg reagent and 25 mg carbon	5.73	~ 33%

All samples had a 23 mm long sleeve 102 in the filter portion and a 7 mm long mouthpiece filter 104. In Sample 2, the second sleeve 74 containing the APS silica gel was located in the tobacco rod adjacent the filter portion and had an inner diameter of 4.0 mm. In Samples 3-5, a second sleeve 74 similar to that of Sample 2 but without the APS silica gel had an inner diameter of 3.5 mm.

Example 6

Cigarettes were constructed in accordance with the plug-space-plug embodiment shown in Figure 5. In each cigarette, the tubular free-flow filter element 20 was 13 mm long, the filter plug 8 was 5 mm long, the filter plug 16 was 7 mm long, and the void space 18 was 5 mm long. Control Samples 1 and 3 contained 50 mg of silica gel without any APS silica gel in the void space 18 and Samples 2 and 4 included APS silica gel particles weighing 50 mg in the void space 18. WS was measured and the results are shown in Table 6 below.

Table 6

SAMPLE	WS
1 (Control)	~ 50%
2	~ 87%
3 (Control)	~ 78%
4	over 93%

Example 7

The cigarettes used for Samples 2 and 3 in Table 7 below were constructed in accordance with the embodiments shown in Figures 6 and 7, respectively. In Sample 2, the tubular filter element 20 was 16 mm long, the filter plug 8 was 7

-20-

mm long, and the solid plug 22 was 7 mm long and comprised of a hand rolled mixture of APS silica gel and polypropylene fibers. In Sample 3, the plug 24 was 23 mm long and comprised of a hand rolled mixture of APS silica gel and polypropylene fibers and the filter plug 8 was 7 mm long. Sample 1 was a control cigarette. Measurements were made of TPM and WS. The results are shown in Table 7 below.

Table 7

SAMPLE	TPM	WS
1		
2	3.92	~ 66%
3	Not tested	~ 81%

According to the invention, the surface of silica gel can be chemically modified to achieve desired selective filtration properties. In the case of APS silica gel, the aminopropylsilyl group is attached to the silica gel skeleton by one or more covalent silicon-oxygen-silicon bonds. The primary amine group at the terminal (exposed or free) end of the aminopropylsilyl group readily reacts with aldehydes and ketones. The primary amine reacts with the aldehyde to form an imine and/or other covalently bonded derivatives of the aldehyde. The imine group or other covalently bonded derivative of the aldehyde remains anchored to the silica gel and thus the formation of such derivatives serves to effectively remove the aldehydes and ketones and their reaction products from cigarette smoke. The primary amine group also reacts with hydrogen cyanide through an acid-base reaction thus reducing the levels of this compound in the cigarette smoke.

Silica gel is a variably hydrous form of silicon dioxide sometimes called "silicic acid" which can be prepared by precipitation by an acid from a solution of sodium silicate. The silica gel can be characterized as a porous disordered three-dimensional polymer of siloxane tetrahedra, forming sheets, ribbons, chains and

-21-

frameworks with various pore-sizes permeating the whole, formed by the variable nature of the cross-linking of the overall three-dimensional structure. Each silicon atom is bonded to four oxygen atoms, at the corners of a tetrahedron. The oxygen atoms are mostly bonded to two silicon atoms but some can be bonded to a single silicon atom and one hydrogen atom to generate a "silanol" functionality. The majority of oxygen atoms are "siloxane" oxygen atoms which are bonded to two silicon atoms. Some silicon atoms called "germinal" silanediols are bonded to two silanol oxygens. The vast majority of silanol groups consist of a silicon atom with one hydroxyl group and three siloxane oxygens. Such silanols may be isolated from one another but when adjacent each other are referred to as "vicinal" silanols (oxo-bis-silanols). Any such silanol functionality provides a point of attachment for derivatizing groups such as 3-aminopropylsilyl. Figure 10 shows a graphic representation of silica gel wherein the typical Si-O-Si bond angle is 145° , the Si-O bond length is about 1.62 \AA and the typical Si-Si distance is about 3.06 \AA .

APS silica gel can be characterized as silica gel which has been modified at some of the hydroxyl groups by the derivatizing reagent 3-aminopropyltriethoxysilane which permanently attaches 3-aminopropylsilyl (APS) groups to the porous silica gel framework. The attached 3-aminopropylsilyl groups can react with targeted carbonyl group containing substrates. Figure 11 shows a graphic representation of APS silica gel wherein the typical Si-O-Si bond angle is 145° , the Si-O bond length is about 1.62 \AA and the typical Si-Si distance is about 3.06 \AA . The 3-aminopropylsilyl groups can be considered basic in that they can remove acids such as hydrogen cyanide from mainstream cigarette smoke. In preparing such APS silica gel it is preferred that the silica gel have a large average pore diameter. For instance, whereas "desiccant" silica gel has a pore size on the order of 20 \AA , a preferred pore size for the APS silica gel is on the order of 60 to 150 \AA . Large pore-sized silica gel can be obtained from the

-22-

Davison Chemical Division of the W.R. Grace & Company, Baltimore, Maryland.

One technique for making such large pore-sized silica gel is by mixing a sodium silicate solution with dilute sulfuric acid, allowing the solution to gel over time, washing with water (for several days), drying and grinding the silica gel. In converting the silica gel into APS silica gel, the silica gel of the desired particle size can be heated with the derivatizing reagent 3-aminopropyltriethoxysilane in a solvent such as water, ethanol, toluene or the like, and heat-drying the reaction product to "cure" the product. Any unused reagent can be recycled during production of other batches of APS silica gel.

The APS silica gel can be prepared using other derivatizing reagents. For instance, another derivatizing reagent which can be used is 3-aminopropyltrimethoxysilane which generates methanol during the manufacturing process. In contrast, 3-aminopropyltriethoxysilane generates ethanol. In addition, the silica gel can be modified to incorporate groups in addition to or instead of the APS. For example, the silica gel can be modified to form aminoethylaminopropylsilyl (AEAPS) silica gel which can be made using N-[3-(trimethoxysilyl)propyl]-ethylenediamine (Chemical Abstracts Service Registry No. 1760-24-3) as the derivatizing reagent. Figure 12 depicts the chemical structures of the starting silane and the final AEAPS silica gel. Alternatively, the silica gel can be modified to form aminoethylaminoethylaminopropylsilyl (AEAEAPS) silica gel which can be made using N¹-[3-(trimethoxysilyl)propyl]-diethylenetriamine (Chemical Abstracts Service Registry No. 35141-30-1) as the derivatizing reagent. Figure 13 depicts the chemical structures of the starting silane and the final AEAEAPS silica gel. The above described APS, AEAPS and AEAEAPS surface modified silica gels can be made in commercial quantities by economic manufacturing conditions. It is contemplated that any covalently bonded amine group attached to silica such as homologues or analogues with

-23-

additional amine functionality can also be used as a component of an air filter such as a cigarette filter in accordance with the invention.

During filtration, the APS silica gel can permanently remove select gaseous components from an airstream such as mainstream tobacco smoke. For instance, by incorporating the APS silica gel in a cigarette filter, cigarette paper, tobacco filler and/or tobacco containing sheet material of a cigarette, the APS silica gel can be used to selectively remove formaldehyde from tobacco smoke. Figure 14 shows a chemical formula representation of how the formaldehyde can be chemically bonded to the APS silica gel when cigarette smoke comes into contact with the APS silica gel.

While the invention has been described so far with reference to a cigarette filter, the invention also provides a filter which is effective in removing a component of a gas mixture such as ambient air by chemically reacting a reagent therewith. As in the case of the cigarette filter described above, the reagent of the air filter preferably comprises at least one reactive functional group. Once the targeted ambient air component chemically reacts with the reagent, the reagent or its reaction product cannot pass into the gas mixture since the functional group is covalently bonded to an inorganic non-volatile substrate.

According to a preferred embodiment, the reagent is incorporated in a gas phase permeable filter for home applications such as ductless range hoods, room air purifiers, electronic air cleaners, air conditioners, and heating/ventilating systems. The filter can also be used in commercial/industrial applications where fuel exhaust and/or manufacturing operations generate odorants such as sulfur dioxide, formaldehyde, phenols, etc. The filter according to the invention can be incorporated in a filter arrangement which also removes smoke, dust, or other particulates. The filter can include odor removing material in the form of flakes, particles, pellets or granules. The filter can include known filter materials such as activated carbon flakes or granules or other substances such as impregnated activated alumina. The gas phase permeable portion of the filter can be made of

-24-

various materials such as fiberglass or open cell polyurethane. The reagent according to the invention can be incorporated in such filters by a variety of techniques, some of which are described above in connection with the cigarette filter and additional techniques are described below. In a preferred embodiment, the reagent comprises the amino-modified silica gel such as APS, AEAPS or AEAEAPS discussed above in connection with the cigarette filter.

According to one embodiment of the invention, the amino-modified silica gel is coated onto a substrate forming part of an air filter. For example, the amino-modified silica gel can be coated on an air permeable portion of the air filter. Alternatively, the amino-modified silica gel can be coated on or entrained in a fibrous material such as cotton, glass wool, rock wool, chopped polyolefin, nylon, polyester, rayon and other fibers, etc. The fibrous material can be in the form of a filament, yarn, ribbon, sheet, etc. of organic or synthetic material. A preferred method of coating a strand of fibrous material is by passing the strand through an adhesive and then through a bed of the amino-modified silica gel particles to attach the amino-modified silica gel particles to the strand. The strand can be incorporated in a filter element by various techniques which will be apparent to those skilled in the art, e.g., the strand can be chopped into pieces which are mixed with other materials to form a filter element or the strand can be formed into a woven or non-woven fabric which is incorporated into a filter element. However, a filter element can be dipped or sprayed with a solution of the APS silica gel, e.g., a solution of the amino-modified silica gel can be sprayed or spread onto a nonwoven material such as paper, polyolefin, polyester, nylon, rayon, glass fiber web, a woven cloth or fabric or screening material including drapery or netting of organic or inorganic materials. Any technique by which the amino-modified silica gel can be incorporated into an air filter is considered within the scope of the invention.

The amino-modified silica gel can also be used as loose particles contained in an air permeable enclosure such as a permeable bag or perforated container

-25-

which can be suspended in open air, hung on a wall, supported on a shelf or placed in an airstream traveling to or from an air conditioning or heating system. However, the amino-modified silica gel particles can also be bonded to one or both sides of an air permeable substrate which can be used alone or in a stack of such substrates as part of an air filter. Another possibility is to bond the amino-modified silica gel particles to each other to form a three dimensional air filter element which is self supporting or supported by another part of an air filter.

According to a preferred embodiment, the amino-modified silica gel is incorporated in a replaceable air filter element. For example, such an air filter can be part of a portable air filtration system or a replaceable filter cartridge or panel of a heating/air conditioning unit. It is contemplated that the air filter could be used in homes, offices, hospitals, schools, governmental or commercial buildings, universities, manufacturing facilities, and the like. The filter will be especially useful in treating the air in newly constructed or remodeled facilities wherein formaldehyde is an obnoxious pollutant produced by gaseous release from resin used in particle board or plywood or by urea-formaldehyde foam insulation used in building or furniture construction. That is, the urea-formaldehyde resin commonly used in plywood/particle board and foam insulation can release gaseous formaldehyde into the ambient air in sufficient quantities to cause irritation or even serious medical problems for certain people exposed to the pollutant. The amino-modified silica gel according to the invention is highly advantageous in reducing or eliminating formaldehyde in the ambient air.

According to one embodiment of the invention, amino-modified silica gel consists of large pore-size silica gel, which has been modified by the covalent chemical attachment of 3-aminopropylsilyl groups thereto (i.e., APS silica gel). The APS silica gel is effective for irreversibly binding ambient aldehydes, permanently anchoring them (after chemical reaction) to the silica gel in non-volatile form. Thus, for the purpose of unencumbered reaction with gaseous components, the amine-group of the 3-aminopropyl substituent is left "free"

-26-

instead of being further modified by derivatizing reagents. A packed bed of moderately coarse granular APS silica gel, of sufficient depth to provide adequate contact-time with minimal pressure-drop, can be used to effectively filter aldehydes from large volumes of ambient air in an efficient manner.

5 In a first preferred embodiment, the reagent such as APS silica gel is incorporated in an air filter such as a 16 inch x 20 inch x 1 inch fiberglass air filter. The air filter can be made of gas phase permeable substrate materials other than fiberglass and the air filter can include ingredients for selectively removing airstream components other than aldehydes. For example, the reagent such as
10 APS silica gel can be loaded onto supports such as activated carbon or charcoal, alumina, woven or non-woven fabric, polyurethane foam, polymeric, ceramic, metallic, and organic materials such as cellulose acetate. The support is preferably in the form of a sheet or mat of material or composite of loose or bonded particles. Figure 15 illustrates a filter 30 having an air permeable filter
15 element 32 containing APS silica gel and a frame 34 surrounding the filter element.

Figure 16 shows a processing line 40 wherein a strand 42 of fibrous material is passed through a bath 44 of adhesive and then through a bed 46 of APS silica gel particles whereby APS silica gel particles are adhered to the strand 42.
20 As indicated earlier, the strand can be chopped into pieces and used alone or mixed with other materials as part of a filter element, e.g., the chopped fibers can be mixed with fiberglass and the fiber mixture can be formed into a filter element such as the filter element 32 shown in Figure 15.

Another technique for forming filter elements having amino-modified silica
25 gel incorporated therein is by papermaking techniques wherein the amino-modified silica gel particles are mixed with the pulp used to form the paper or the amino-modified silica gel can be applied as a coating to the paper after it is formed. The paper coating technique offers advantages in achieving a desired amount of the amino-modified silica gel in a filter element, e.g., by controlling the coated

-27-

amount of reagent/area of the paper and/or the total area of coated paper employed in the filter (e.g., higher amounts of amino-modified silica gel can be provided simply by using larger pieces of coated paper or heavier coatings on the paper).

5 The reagent such as amino-modified silica gel can be incorporated into filter paper in a number of ways. For example, the amino-modified silica gel can be mixed with water to form a slurry. The slurry can then be coated onto pre-formed filter paper and allowed to dry. The filter paper can then be incorporated into an air filter as a single layer or as part of a multi-layer composite wherein the
10 filter paper is an outer or inner layer of the composite. Alternatively, the dried paper can be molded into a three dimensional shape or wrapped into an air permeable cylindrical shape. In another arrangement, the paper can comprise a liner of air filter. If the amino-modified silica gel is added to the ingredients of filter paper during the paper-making process, the amino-modified silica gel can be
15 mixed with bulk cellulose to form a cellulose pulp mixture and the mixture can then be formed into filter paper according to methods known in the art.

 Various techniques can be used to apply the reagent such as amino-modified silica gel to filter fibers or other substrate supports. For example, the amino-modified silica gel can be added to the filter fibers before they are formed
20 into a filter element, e.g., the amino-modified silica gel can be added to the filter fibers, for example, in the form of a dry powder or a slurry by methods known in the art. If the amino-modified silica gel is applied in the form of a slurry, the fibers may be dried before they are formed into a filter element.

 In another preferred embodiment, the reagent such as amino-modified
25 silica gel is employed as a mass of particles in an air permeable enclosure. However, the particles of the amino-modified silica gel can be mixed with other materials such as substances which filter other components from the air. The amino-modified silica gel can be in granular form or loaded onto a support

-28-

material such as a paper, organic or inorganic particulate material, fibers, thread, etc.

As explained above, the amino-modified silica gel can be incorporated in various support materials. When the amino-modified silica gel is used in filter paper, the silica gel beads or particles may have an average particle diameter of 10 to 100 μm , preferably 40 to 50 μm . When the amino-modified silica gel is used in filter fibers or other mechanical supports, larger silica gel particles may be used. Such particles preferably have a mesh size from 14 to 60, and more preferably from 35 to 60 mesh. The silica gel particles preferably have an average pore size of about 40 to about 250 \AA , and more preferably, about 150 \AA . An advantage of the APS silica gel reagent according to the invention is that formaldehyde can be selectively and permanently removed from the ambient air. In contrast, formaldehyde removed from an airstream by filter materials such as unmodified silica gel (i.e., silica gel without the APS) absorb rather than chemically react with the formaldehyde. As a result, formaldehyde absorbed by such unmodified silica gel could release the formaldehyde back into the airstream.

Figure 17 shows results of tests carried out to determine the formaldehyde absorbing ability of various amino-modified silica gels. In the results shown in Figure 17, curve A represents mercaptopropylsilane MPS corresponding to the formula: $\equiv\text{Si-CH}_2\text{-CH}_2\text{-CH}_2\text{-SH}$, curve B represents AEAEAPS corresponding to the formula: $\equiv\text{Si-CH}_2\text{-CH}_2\text{-CH}_2\text{-NH-CH}_2\text{-CH}_2\text{-NH-CH}_2\text{-CH}_2\text{-NH}_2$, curve C represents AEAPS corresponding to the formula: $\equiv\text{Si-CH}_2\text{-CH}_2\text{-CH}_2\text{-NH-CH}_2\text{-CH}_2\text{-NH}_2$, curve D represents 35x60 mesh APS corresponding to the formula: $\equiv\text{Si-CH}_2\text{-CH}_2\text{-CH}_2\text{-NH}_2$, curve E represents 14x40 mesh APS and curve F represents an additional APS sample. During the tests, 30 mg of amino-modified silica gel was loaded in a non-packed condition in a plug-space-plug configuration wherein a cellulose acetate filter was used as a holder for the sample. The length of the filter bed can be calculated based on the packing density of the amino-modified silica gel sample and diameter of the holder. Using 22 pounds/cubic

-29-

foot (5775 mg/in^3) as the density of the silica gel, the volume of the 30 mg sample is calculated as 0.0052 in^3 , the measured flow rate of the gas stream (a predetermined amount of formaldehyde in nitrogen) was $160 \text{ cm}^3/\text{min}$, and the contact time was calculated as 32 ms. Curves A and B are estimated to terminate at about 0.016 Absorbance Units (AU) corresponding to formaldehyde concentrations of about 48 ppm, curves C and D are estimated to terminate at about 0.014 AU corresponding to formaldehyde concentrations of about 42 ppm, and curve E is estimated to terminate at about 0.013 AU corresponding to formaldehyde concentrations of about 39 ppm. According to the U.S. Environmental Protection Agency, formaldehyde levels as low as 0.1 ppm can cause "watery eyes, burning sensations in the eyes and throat, nausea, and difficulty breathing in some humans." Although the results shown in Figure 17 were not conducted at such low formaldehyde levels, the results demonstrate that an air filter containing the amino-modified silica gel according to the invention should be capable of removing low levels of formaldehyde from ambient air. For example, in adapting the air filter according to the invention for air purification of a standard room size, an air flow rate of $30 \text{ ft}^3/\text{min}$ could be used to filter air through a 15 inch by 9.5 inch air filter in accordance with the invention.

From the foregoing test results it is estimated that 1 mol of the AEAPS traps 2 mols of formaldehyde gas. With respect to the shapes of the curves in Figure 17, the longer the curve stays low (i.e., the curve is closer to 0 AU), the higher the capacity of the filtration agent. Based on the test results, it appears that AEAPS and AEAEAPS exhibit the best behavior in this regard.

The experiments indicate that the amino-modified silica gel is effective in removing formaldehyde from a gas stream wherein nitrogen is the carrier gas. Such results suggest that the amino-modified silica gel will also remove aldehydes from ambient air, especially in view of the results discussed above with respect to removal of aldehydes from cigarette smoke which is an air stream containing tobacco smoke. Further, the filter according to the invention can be used to

-30-

remove select gaseous components from non-air streams such as waste gas streams in industrial processes. Accordingly, the filter according to the present invention can be used for a wide assortment of filtering applications.

While the invention has been described with reference to preferred
5 embodiments, it is to be understood that variations and modifications may be
resorted to as will be apparent to those skilled in the art. Such variations and
modifications are to be considered within the purview and scope of the invention
as defined by the claims appended hereto. For example, the ring structure
depicted in Figure 9 is representative of a wide range of ring sizes present within
10 the highly disordered silica gel structure, and is not intended to exclude other sizes
of ring from consideration as components of the matter covered by this patent
application.

-31-

Claims:

1. A filter comprising a reagent consisting essentially of at least one reactive functional group covalently bonded to a non-volatile inorganic substrate wherein the reagent chemically reacts with a gaseous component of a gas stream to remove
5 the gaseous component from the gas stream.
2. The filter according to claim 1, wherein the reagent comprises a coating on a filter element or a coating on a strand of fibrous material forming a filter element or particles such as silica gel or a shaped article.
3. The filter according to claim 1, wherein the functional group is an
10 aminopropylsilyl group such as a 3-aminopropylsilyl group or a N-[2-aminoethyl]-3-aminopropylsilyl group or a N-[3-aminoethyl]-3-aminopropylsilyl group or a N-[N-(2-aminoethyl)-2-aminoethyl]-3-aminopropylsilyl group.
4. The filter according to claim 1, wherein the substrate comprises filter fibers and the reagent is covalently bonded to the filter fibers preferably in an
15 amount of 10 to 50% by weight.
5. The filter according to claim 1, wherein the gaseous component to be removed is polar such as an aldehyde.
6. The filter according to claim 1, wherein the reagent is incorporated in filter paper optionally arranged as adjacent layers in the filter or folded into a three-
20 dimensional shape or arranged as a single layer in the filter.
7. The filter according to claim 1, wherein the reagent is incorporated with cellulose acetate fibers and/or polypropylene fibers.

-32-

8. The filter according to claim 1, wherein the reagent is incorporated in a cavity of the filter or the reagent is incorporated in a carpet or drapery material.

9. The filter according to claim 1, wherein the filter comprises a replaceable filter element of an air ventilation system.

5 10. A filter which comprises an amino-modified silica gel wherein the functional group is an aminopropylsilyl group or an aminopropylsilyl group further substituted on nitrogen by one or more aminoalkyl or poly(aminoalkyl) functional groups.

10 11. The filter according to claim 10, wherein the filter is incorporated in an air ventilation system.

12. The filter according to claim 11, wherein amino-modified silica gel comprises an aminopropylsilyl group covalently bonded to the silica gel.

15 13. The filter according to claim 12, wherein the functional group includes a 3-aminopropylsilyl group or a N-[2-aminoethyl]-3-aminopropylsilyl group or a N-[3-aminoethyl]-3-aminopropylsilyl group or a N-[N-(2-aminoethyl)-2-aminoethyl]-3-aminopropylsilyl group.

14. The filter according to claim 10, wherein the amino-modified silica gel comprises a coating on a filter element or a coating on a strand of fibrous material forming a filter element or particles such as silica gel or a shaped article.

20 15. The filter according to claim 10, wherein the amino-modified silica gel is incorporated in filter paper optionally arranged as adjacent layers in the filter or folded into a three-dimensional shape or arranged as a single layer in the filter.

-33-

16. The filter according to claim 10, wherein the amino-modified silica gel is incorporated with cellulose acetate fibers and/or polypropylene fibers.
17. The filter according to claim 10, wherein the amino-modified silica gel is incorporated in a cavity of the filter or the reagent is incorporated in a carpet or
5 drapery material.
18. The filter according to claim 10, wherein the filter comprises a replaceable filter element of an air ventilation system.
19. The filter according to claim 10, wherein the amino-modified silica gel has an average particle diameter of at least 10 μm or the amino-modified silica gel is
10 in the form of particles having a mesh size of at least 60.
20. The filter according to claim 10, wherein the total nitrogen content of the amino-modified silica gel is in the range of approximately 1 to 3 percent by weight, preferably 1.5 to 2.1 percent by weight.
21. A method of manufacturing a filter which is useful for removing a gaseous
15 component of a gas mixture, comprising steps of:
 preparing a reagent comprising at least one reactive functional group covalently bonded to a non-volatile inorganic substrate; and
 incorporating the reagent in a filter wherein the reagent chemically reacts with a gaseous component of a gas mixture to remove the gaseous component
20 from the gas mixture.
22. The method according to claim 21, wherein the reagent is effective in removing a polar gaseous component such as an aldehyde from the gas mixture.

-34-

23. The method according to claim 21, wherein the reagent is prepared such that the functional group includes a 3-aminopropylsilyl group or a N-[2-aminoethyl]-3-aminopropylsilyl group or a N-[3-aminoethyl]-3-aminopropylsilyl group or a N-[N-(2-aminoethyl)-2-aminoethyl]-3-aminopropylsilyl group.

5 24. The method according to claim 23, wherein the reagent is prepared by reacting silica gel with an aqueous or non-aqueous solution containing 3-aminopropyltriethoxysilane or 3-aminopropyltrimethoxysilane or N-[3-(trimethoxysilyl)propyl]-ethylenediamine or N¹-[3-(trimethoxysilyl)propyl]-diethylenetriamine.

10 25. The method according to claim 21, wherein the functional group is an aminopropylsilyl group such as a 3-aminopropylsilyl group.

26. The method according to claim 21, wherein the reagent is incorporated in the filter by coating the reagent on a filter element or coating the reagent on a strand of fibrous material forming a filter element.

15 27. The method according to claim 21, wherein the substrate comprises filter fibers and the reagent is covalently bonded to the filter fibers preferably in an amount of 10 to 50% by weight.

28. The method according to claim 21, wherein the reagent is incorporated in filter paper optionally arranged as adjacent layers in the filter or folded into a
20 three-dimensional shape or arranged as a single layer in the filter.

29. The method according to claim 21, wherein the reagent is incorporated with cellulose acetate fibers and/or polypropylene fibers.

-35-

30. The method according to claim 21, wherein the reagent is incorporated in a cavity of the filter or the reagent is incorporated in a carpet or drapery material.
31. The method according to claim 21, wherein the filter comprises a replaceable filter element of an air ventilation system.
- 5 32. The method according to claim 21, wherein the reagent comprises amino-modified silica gel having an average particle diameter of at least 10 μm or the reagent comprises amino-modified silica gel in the form of particles having a mesh size of at least 60.
- 10 33. The method according to claim 32, wherein the total nitrogen content of the amino-modified silica gel is in the range of approximately 1 to 3 percent by weight, preferably 1.5 to 2.1 percent by weight.
- 15 34. A method of removing a gaseous component of a gas mixture, comprising passing the gas mixture in contact with a filter comprising a reagent comprising at least one reactive functional group covalently bonded to a non-volatile inorganic substrate such that the reagent chemically reacts with the gaseous component of the gas mixture and removes the gaseous component from the gas mixture.
- 20 35. The method according to claim 34, further comprising steps of generating the gas mixture and directing a gas stream containing the gas mixture into contact with the filter such that the component of the gas mixture to be removed is chemically reacted with the reagent and prevented from reentering the gas stream.
36. The method according to claim 34, wherein the functional group is an aminopropylsilyl group effective to remove an aldehyde component from the gas

-36-

mixture, the gas mixture being passed into contact with the reagent such that the aldehyde component is removed from the gas mixture.

37. The method according to claim 34, wherein the functional group is a 3-aminopropylsilyl group effective to remove formaldehyde from the gas mixture, the gas mixture being passed into contact with the reagent such that the formaldehyde is removed from the gas mixture.

38. The method according to claim 34, wherein the reagent comprises amino-modified silica gel located in one or more filter elements, the gas mixture being passed into contact with the one or more filter elements.

39. The method according to claim 34, wherein the substrate comprises particles or a shaped article, the gas mixture being passed into contact with a mass of the particles or into contact with the shaped article.

40. The method according to claim 34, wherein the reagent is incorporated in filter paper optionally formed into a three-dimensional shape or the reagent is combined with fibers which are formed into a filter element, the gas mixture being passed into contact with the filter paper or the filter element.

41. The method according to claim 34, wherein the reagent is combined with an air permeable filter body, the gas mixture being passed into contact with the filter body such that the reagent chemically reacts with the gaseous component and removes the gaseous component from the gas mixture.

42. The method according to claim 34, wherein the substrate comprises filter fibers such as polypropylene and/or cellulose acetate fibers and the reagent is covalently bonded to the filter fibers in an amount of 10 to 50% by weight, the

-37-

gas mixture being passed into contact with the filter fibers such that the gaseous component reacts with the reagent and the gaseous component is removed from the gas mixture.

43. The method according to claim 34, wherein the functional group includes a 3-aminopropylsilyl group or a N-[2-aminoethyl]-3-aminopropylsilyl group or a N-[3-aminoethyl]-3-aminopropylsilyl group or a N-[N-(2-aminoethyl)-2-aminoethyl]-3-aminopropylsilyl group, the gas mixture being passed into contact with the reagent.

44. The method according to claim 34, wherein the reagent comprises amino-modified silica gel having a total nitrogen content in the range of approximately 1 to 3 percent by weight, preferably 1.5 to 2.1 percent by weight, the gas mixture being passed into contact with the reagent.

45. The method according to claim 34, wherein the reagent is incorporated in a cavity of the filter or the reagent is incorporated in a carpet or drapery material, the gas mixture being passed into contact with the reagent.

46. The method according to claim 34, wherein the filter comprises a replaceable filter element of an air ventilation system, the gas mixture comprising ambient air passed into contact with the filter element.

47. The method according to claim 34, wherein the reagent comprises amino-modified silica gel having an average particle diameter of at least 10 μm or amino-modified silica gel in the form of particles having a mesh size of at least 60, the gas mixture being passed into contact with the reagent.




FIG. 1




FIG. 2




FIG. 3

2/11




FIG. 4




FIG. 5




FIG. 6




FIG. 7




FIG. 8

4/11




FIG.9




FIG.10

6/11




FIG. 11

7/11




FIG. 12

8/11




FIG. 13

9/11




FIG. 14




FIG. 15




FIG. 16

11/11




FIG. 17

INTERNATIONAL SEARCH REPORT

International application No.

PCT/US99/25427

A. CLASSIFICATION OF SUBJECT MATTER

IPC(7) : A24B 15/28; A24B 15/18; A24B 15/00

US CL : 131/332, 334, 331, 202

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

U.S. : 131/332, 334, 331, 202; 423/228, 210, 245.1, 242.7

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

EAST/WEST Electronic On-line Searching

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
Y	US 4,892,719 A (GESSER et al) 09 January 1990, col. 1, lines 6-10; 53-68; col. 2, lines 1-4; 15-35	1-6, 8-28, 30-31, 34-37, 39-43, 45-46
Y	US 4,300,577 A (HORSEWELL et al.) 17 November 1981, col. 1, lines 24-63; col. 2, lines 12-31, see abstract.	1-8, 10-30, 32-47
Y	US 3,003,504 A (TOUEY et al.) 10 October 1961, col.1, lines 9-11, 63-69; col. 5, lines 24-32	7,29, 42



Further documents are listed in the continuation of Box C.



See patent family annex

* Special categories of cited documents:	*T* Later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
A document defining the general state of the art which is not considered to be of particular relevance	*X* document of particular relevance, the claimed invention cannot be considered novel or non-obvious, considered to involve an inventive step when the document is taken alone
E earlier document published on or after the international filing date	*Y* document of particular relevance, the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art
L document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)	*Z* document member of the same patent family
O document referring to an oral disclosure, use, exhibition or other means	
P document published prior to the international filing date but later than the priority date claimed	

Date of the actual completion of the international search

12 DECEMBER 1999

Date of mailing of the international search report

04 FEB 2000

Name and mailing address of the ISA/US
Commissioner of Patents and Trademarks
Box PCT
Washington, D.C. 20231

Facsimile No. (703) 305-3230

Authorized officer

DIONNE A. WALLS

Telephone No. (703) 308-0661